BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/03/2019-20 Dated: 18-5-2019

APPROVED TENDER SCHEDULE –'B'

Item-03

Name of Work:-Construction of Meeting Hall in Shankarnag Park in ward No:04 Of Yelahanka satellite town sub division

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3) SR 2018-19	cum	63.36	322.11	Rupees Three Hundred Twenty Two and Paise Eleven Only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1) SR 2018-19	cum	63.36	87.34	Rupees Eighty Seven and Paise Thirty Four Only
3	KSRB4.1.3: Providing and laying position plain cement concrete of Mix 1:4:8 with OPC cement @180Kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregtes @ 0.57 cum machine mixed , concrete laid in layers not exeecding 15 cms, thick, well compacted , in foundation , including cost of all materials, Labour , HOM of Machinery, Curing complete as per Specifications. Specifications No. KBS 4.1, 4.2 (P12/4.3). SR 2018-19	Cum	54.82	5496.38	Rupees Five Thousand Four Hundred Ninety Six and Paise Thirty Eight Only
4	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Sqm	33.60	4951.27	Rupees Four Thousand Nine Hundred Fifty One and Paise Twenty Seven Only
5	Providing and laying /fixing cement base. Precast, pre polished cement concrete designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treds of steps and landing, laid on bed of 12mm thick cement mortal 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting griding the eges to half/full round wherever required. Labour, curing complet as per specification. Page No. 108/ Item No. 14.62 / PWD SR 2018-19	Sqm	252.00	1327.23	Rupees One Thousand Three Hundred Twenty Seven and Paise Twenty Three Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	KSRB 15.1.1: Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(Page No.113/Item No. 15.1)	Sqm	28.00	151.90	Rupees One Hundred Fifty One and Paise Ninety Only
7	KSRRB M300-53: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification Page No. 305.4.3, No. 156/ Item No. 19.60/ PWD SR 2018-19	cum	90.00	350.12	Rupees Three Hundred Fifty and Paise Twelve Only
8	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2018-19	Cum	27.96	6096.44	Rupees Six Thousand Ninety Six and Paise Forty Four Only
9	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. TMT bars Fe 500 KBS 4.6.3 Page No. 18/ Item No. 4.46/ PWD SR 2018-19	Tonne	0.84	76451.67	Rupees Seventy Six Thousand Four Hundred Fifty One and Paise Sixty Seven Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.B B UMESHA (SMLP Asphalts)	
				Rate	Rate in Words
	Fabricating supplying and erecting M.S. TubulerTruss of span upto 10m bottom and top member is provided with 50x50x6mm double equale angles, welded back to back and in between top and bottom line, in ereas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided all the members are weldeded toghter with 6mm gusset plate as per drawing, The enter truss is anchored in RCC column buy using 4Nos of M.S anchor bolts at eacth support, with 10mm thick base plate and shoe plate. The work includes cutting, straightening , pacing in position of M.S angle and welding wherever necessary, and applying one of red oxide primer coat to all the members including cost of all materials, labour charges,and higher charges of mechineries for cutting welding, granding and erection equipments, with all lead and lift, transportation, etc, complete as per specification. Page No. 45/ I No. 7.29/ PWD SR 2018-19	Kgs	11257.49	119.58	Rupees One Hundred Nineteen and Paise Fifty Eight Only
11	PROVIDING TRAPEZOIDAL PROFILED SHEET Providing and installing of pre painted Galvolume iron Trpezoidal profiled sheet of approved make 1060mm width (1000mm cover width), 28-30 mm crest height with cest distance of 200 mm c/c with 2ribs at the center for stiffening , The total coated thickness (TCT) of the sheet will be 0.47 mm +/- 0.02 mm tolerance Zinc –Alu Alloy coating AZ 150 gsm as pe ASTM 1397/A755-550 mpa steel grade. 5-7 microns epoxy primer on both side of the sheet and polyester top coat 20-22 microns using self drilling /self tapping screws of 25mm length,to be fixed over the existing purlins, rafters channel and trusses. No. 300/ Item No. 38.30 PWD SR 2018-19	sqm	300.00	741.18	Rupees Seven Hundred Forty One and Paise Eighteen Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.